

RA No	Hazard	Risk(s)
RA 043	Removing retaining walls at storage facilities	Crush Injury Property Damage
Risk Rating		
Probability	Severity	Risk Rating
Likely-4	High-5	High Risk-20
Control Measures		
<ul style="list-style-type: none"> - Only trained individuals to carry out this work (must have teleporter cert and slinging principles training). - No obstacles left in or around the work area. - Safety chains to be certified safe for use. - GA1 cert on teleporter. - If a ladder is required, the ladder must be fit for purpose and staff must be trained in its use. (RA 024) - It's a 2-man job and must not be attempted by one individual. 		
Additional Control Measures		
<ul style="list-style-type: none"> - Safety signage provided at all sites - Emergency procedures provided at all sites - First Aid kits provided at all sites - PPE provided 		
Frequency		Duration
Monthly		Short
Final Risk Rating		
Probability	Severity	Final Risk Rating
Very Unlikely-1	High-5	Low Risk-5

In accordance with Health and Safety Act 2005